



STATE	3	STACK HEIGHT
FREE	1	0.0905
INSTALLED	2	0.0870

NOTES: (UNLESS OTHERWISE SPECIFIED)

- FREE STATE REQUIRES MEASUREMENT WITH MINIMAL FORCE APPLIED FROM THE MEASUREMENT DEVICE. WHEN A RING SHIM IS PRESENT, THE MEASUREMENT DEVICE MUST SPAN BOTH SIDES OF THE RING SHIM.
- INSTALLED STATE REQUIRES COMPRESSING THE VALVE STACK TO SOLID HEIGHT USING COMPRESSION INTERFACES THAT ARE NO LARGER IN DIAMETER THAN THE MINIMUM VALVE DIAMETER.
- FREE STATE AND INSTALLED STATE VALUES WILL BE IDENTICAL WHEN NO RING SHIM IS PRESENT.

PROPRIETARY - THIS DOCUMENT CONTAINS CONFIDENTIAL, PROPRIETARY INFORMATION THAT IS FOX PROPERTY. DO NOT DISCLOSE TO OR DUPLICATE FOR OTHERS EXCEPT AS AUTHORIZED BY FOX.

FOX Factory, Inc. Ph 831-768-1100
 130 Hangar Way, Watsonville, CA 95076 USA Fax 831-768-9312

TITLE: **Valve Stack Assy: 2018 FLOAT DPX2, CLA001**

SIZE DWG. NO. **C 805-05-372-KIT**

PLOT SCALE 1:1:1 SHEET 1 OF 1